Material Estimate

Generated: Apr 21, 2026, 12:44 PM

1. Roof summary

Field	Value
Plan area (total)	2500 sq ft
Pitched area	1500 sq ft
Flat area	1000 sq ft
Roof pitch (rise / 12)	8
Complexity	Medium
Shingle style	3-Tab
Preferred brands	CertainTeed
Flat roofing system	EPDM
Ridge length	120 LF
Hip length	80 LF
Valley length	60 LF
Eave length	140 LF
Rake length	100 LF
Surface area (combined)	2500 sq ft
Suggested waste (pitched)	14.30%
Suggested waste (flat)	4.90%

2. Material estimate (grouped by item)

Pitched roof

Pitch: 8 (rise / 12) · Suggested waste (model): 14.30% · Custom waste (ordering column): 15.00%

Product	Unit	Basis	Waste (0%)	Waste (10%)	Waste (suggested 14.30%)	Waste (15%)	Unit price	Line total
Drip Edge			240 ft	264 ft	274 ft	276 ft		
No Brand - Eave Drip Edge (10 ft section)	pieces	10 ft sections	14	16	17	17	$8.00	$136.00
No Brand - Rake Drip Edge (10 ft section)	pieces	10 ft sections	10	12	12	12	$8.00	$96.00
Fasteners			—	—	—	—		
No Brand - Plastic Caps	caps	120/square	1800	1981	2058	2070	$0.01	$20.70
No Brand - Roofing Nails 1-1/4 in	nails	320/square	4800	5281	5487	5520	$0.01	$55.20

Flashing			240 ft	264 ft	274 ft	276 ft		
No Brand - Step Flashing	rolls	~75 LF/roll	2	3	3	3	$65.00	$195.00
No Brand - Valley Flashing	rolls	~75 LF/roll	1	1	1	1	$65.00	$65.00
Ice & Water			200 ft	220 ft	229 ft	230 ft		
CertainTeed - WinterGuard	rolls	65 LF/roll	4	4	4	4	$120.00	$480.00
Ridge Cap			200 ft	220 ft	229 ft	230 ft		
CertainTeed - Mountain Ridge	bundles	20 LF/ bundle	10	12	12	12	$45.00	$540.00
CertainTeed - Shadow Ridge	bundles	31 LF/ bundle	7	8	8	8	$45.00	$360.00
CertainTeed - Shangle Ridge (Luxury)	bundles	31 LF/ bundle	7	8	8	8	$45.00	$360.00
Sealant			—	—	—	—		
No Brand - Caulking (Roof Sealant)	tubes	1 tube / 5 squares	3	4	4	4	—	—
Shingles			1500 sqft	1650 sqft	1715 sqft	1725 sqft		
CertainTeed - Grand Manor (Luxury)	bundles	25 sq ft/ bundle	60	67	69	69	$35.00	$2415.00
CertainTeed - Landmark	bundles	32.8 sq ft/ bundle	46	51	53	53	$35.00	$1855.00
CertainTeed - Landmark Pro	bundles	32.8 sq ft/ bundle	46	51	53	53	$35.00	$1855.00
CertainTeed - NorthGate	bundles	33.3 sq ft/ bundle	46	50	52	52	$35.00	$1820.00
CertainTeed - Presidential Shake (Luxury)	bundles	25 sq ft/ bundle	60	67	69	69	$35.00	$2415.00
Underlayment			1500 sqft	1650 sqft	1715 sqft	1725 sqft		
CertainTeed - DiamondDeck	rolls	937.5 sq ft/ roll	2	2	2	2	$90.00	$180.00
CertainTeed - RoofRunner	rolls	937.5 sq ft/ roll	2	2	2	2	$90.00	$180.00
Ventilation			—	—	—	—		
No Brand - Roof Vent (1 per 300 sq ft plan area)	units	1 unit per 300 sq ft	5	6	6	6	$25.00	$150.00

Flat roof

System: epdm · Suggested waste (model): 4.90% · Custom waste (ordering column): 15.00%

No products match the selected brands for this section (CertainTeed).

Quantities are estimates for ordering; verify against manufacturer specs, local code, and field conditions.

3. Pricing totals

Subtotal: $3664.60

Margin (20%): $732.92

TOTAL: $4397.52

4. Verification appendix (source + formula)

Field	Value
Catalog source	manufacturer_products (seeded from roofing_material_brand_names.docx)
Suggested waste source	calibrated_dynamic_model
Formula (pitched)	base + complexity_bump + pitch_bump + shape_bump (ridge/hip/valley), capped
Formula (flat)	base + complexity_bump, capped (no pitch/shape term)
Area input type	slope_adjusted
Area handling	plan => applies pitch multiplier; slope_adjusted => no second pitch multiplication
Selected brands	CertainTeed
Custom waste	15.00%

This report is a material takeoff aid, not a contract. Manufacturer, color, warranty, and accessory compatibility must be confirmed before order.